### Unknown

From:

Ronald W. Slovacek [landdevelopment@ez2.net]

Sent:

Monday, May 09, 2005 7:57 AM


To:

'andrealkc@grandecom.net'

Subject:

Laureland proposal-Ron-Slo Inc to LCG 5-6-05

Attachments: Laureland proposal-Ron-Slo Inc to LCG 5-6-05.doc



# RON-SLO, INC.

Wednesday, December 06, 2006

LCG Development 13232 Fall Manor Drive Dallas, Texas 75243

Gentlemen:

**PROPOSAL** 

We propose to furnish all labor, materials, and equipment to construct as an independent contractor, the following described work:

**DESCRIPTION AND LOCATION:** 

Rosemont @ Laureland Towhhomes

Dallas, Texas

BGO Architects LP, Project #04146

Sterling Engineering, Structural Engineer, Project #222-024

Kimley-Horn, Civil Engineer, Project #063881030

ITEM DESCRIPTION	QUANTITY	UNIT	UN	IT PRICE		AMOUNT
Foundations .						god <sup>25</sup> oso g
Construct foundations for 42 buildings as per plans	207876	SQ FT	\$	4.57	\$	949,993.32
Paving		A real less easy a	er anne	POST SAN TAN THE PROPERTY OF THE PROPERTY OF		
Parking - 6"-3600 PSI con. Pavement w/#3 @ 18" ocew	101412	SQ FT	\$	2.79	\$	282,939.48
Fire Lanes- 6"-3600 PSI con. Pavement w/#3 @ 18" ocew	183328	SQ FT	\$	2.79	\$	511,485.12
Dmpstr Pads-7"-3600 PSI con. Pavement w/#3 @ 18" ocew	16248	SQ FT	\$	3.35	\$	54,430.80
10"-4500 PSI con. Pavement w/#3 @ 18" ocew	2250	SQ FT	\$	6.15	\$	13,837.50
10"-5000 PSI con Pavement w/#4 @ 24"j ocew	2400	SQ FT	\$	6.15	\$	14,760.00
Sidewalks		/ (.a. (a)		Section of the section of	ļ	
Construct 4"- 3000 PSI reinforced sidewalk	0	SQ FT	\$	2.39	\$	
Additional Items (per each)		ļ		. 6 Marin V	r.**	
Fence Column Footings (qauntity to be verified)	. 0	EACH	\$	265.00	\$	=
Monument Footings	0	EACH	\$	3,635.00	\$	
Gate Track Footings	Ŏ	LF	\$	27.50	\$	
Light Pole Bases (quantity to be verified)	. 0	EACH	\$	245.00		* ***
Total		i	1		\$	1,827,446.22

Sincerely,

Ronald W. Slovacek President

## RON-SLO, INC.

#### **BID QUALIFICATIONS**

Project Name:

Rosemont @ Laureland Townhomes

Dallas, Texas

- All grade beams to be trenchable with TF 300 Side boom trencher
- Concrete figured @ 3000 PSI w/ Ash
- Excludes any extended Grade Beams
- Excludes any rock excavation
- All paving figured w/ #3's @ 18" o.c.e.w. w/ Saw joints figured @ 15' o.c., w/ hot pour joint sealant.
- Expansion joints @ 90' o.c. w/ hot pour joint sealant
- Includes saw of concrete and existing approaches and C & G for new approaches only.
- Demolition and haul off by others.
- Barricades figures for 1 month for our work
- We exclude any grooved, patterned, or colored concrete
- · We exclude any surveying or backfill of curbs
- We exclude any city walks (see alternate for city walk pricing)
- Light pole bases are subject to change upon quantity confirmation.
- Fence Footings are subject to change upon quantity confirmation

#### THE FOLLOWING ARE SPECIFICALLY INCLUDED FOR THE ABOVE

- · Batter boards, forms, and accessories
- · Reinforcement and accessories
- Anchor Bolts furnished and installed @ 4' on center at slab perimeter (1/2" x 9")
- Concrete pumping @ building slabs only.

#### THE FOLLOWING ARE SPECIFICALLY EXCLUDED FOR THE ABOVE

- Site walls or footings
- Extended Grade Beams @ perimeter
- · Exposed aggregate
- Dirt work (sub grade to be + or 1/10)
- Soil erosion protection
- Excavation or drilling of rock if encountered
- · De-watering as a result of subsurface water
- Casing of piers
- Surveying, engineering, layout—building corners, back of curbs, and blue tops by others
- Saw cutting, demolition or haul off of existing concrete (except as noted)
- Pavers
- Concrete temperature control (heating or ice)
- Masonry reinforcing
- Masonry grouting
- Sawed control joints at foundation
- Embedded materials (anchor bolts, pipe bollards, embedded plates, angles, hold downs, etc.) except as noted
- Testing by labs
- Permits or fees
- Performance or payment bonds
- Wet curing
- Hardeners or sealers
- Drawings for anchor bolt layout
- Removal of trash or concrete spoils from site (we will place in dumpster or designated area)
- Spoil removal off site

318A Dallas Drive/Denton/Texas/76205 Office 940-243-0812/Fax-940-243-0945

### RON-SLO, INC.

- Backfill with select fill (offsite material)
- Backfill at back of curbs
- Soil poisoning
- PVC for electrical or landscaping sleeves
- Sweeping or washing down of pavement
- Concrete wheel stops
- Pavement markings (stripping or buttons)
- Inlets, drains, catch basins, box culverts
- Stair nosing or sleeves for rails
- Repair of existing underground if damaged
- Grouting of thresholds
- · Safety railings or perimeter cables at upper floors, pits, drops, and openings
- Light weight concrete-furnish or install
- Pool decks, mechanical pads or site retaining walls
- · Gate tracks (no details)
- · Any item not on the Bid Schedule

#### Alternates:

Price per SQ FT to demo & haul off city walk

\$2.70 SQ FT

\$3.75 SQ FT

Price per SQ FT to replace city walk

\$12.00 LF

Price per LF to saw/demo & haul off of concrete curb

\$27.50 LF

Price per LF to replace concrete curb

#### Notes:

- If retainage is held, its is to be funded 30 days after completion of each phase of our work
- Proposal to become part of contract
- All material prices only good through 7-11-05, after that time any increase in price will be paid by contractor or owner including sales tax and markup.